

SCHEDULE OF GRAVEYARD SHEDS at NAMODELORA KABIRAJPARA ,JL NO- 43 PLOT NO- 535  
ILLAMBAZAR PANCHAYAT SAMITY JURIDICTION.

AT DHARAMPUR G.P UNDER

Sl no	Description of Item	No	Length	Bredth	Height	Qty.	Total Qty	Unit	Rate(Rs.)	Amount (Rs.)
1.(	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete.									
	Total					10.161	10.161	cum	119.27	Rs. 1,211.90
2.)	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.									
	Total					24.540	24.540	Sqm	266.00	Rs. 6,527.64
3	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)									
	Total					8.871	8.871	cum	487.41	Rs. 4,323.81
4	(I) Cement concrete with graded stone ballast (40 mm size excluding shuttering)(1:3:6) In ground floor									
	Total					1.135	1.135	cum	4233.00	Rs. 4,804.46
5	Ordinary Cement concrete (1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in gound floor as per relevant IS codes.									
	Total					9.123	9.123	cum	5210.55	Rs. 47,535.85
6	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) WITHOUT STAGGING									
	Total					16.640	16.640	Sqm	93.00	Rs. 1,547.52
	HIRE & labour chades for shuttering (with staggng)									
	Total					52.883	52.883	sqm	328.00	Rs. 17,345.62

7	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. @ 0.85 % Steel used in Total Volume of Concrete. =9.123x1.2/100x7850kg= 860 kg					0.860	MT.	66980.95	Rs.	57,603.62
8	Brick work with 1st class bricks in cement mortar (1:6) foundation & plinth					1.635	Cum	4243.00	Rs.	6,937.31
	Brick work with 1st class bricks in cement mortar (1:6) superstructure					1.066	Cum	4466.00	Rs.	4,760.76
						1.066				
9	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] 15mm Thick(6:1)					18.189	Sqm	135.00	Rs.	2,455.52
10	c)Celling Plaster Or Concrete Surface (4:1) 10mm					165.685	Sqm	122.00	Rs.	20,213.57
11	Neat cement punning about 1.5 mm. thick in wall, dado, window, sills, floor, drain etc. NOTE : Cement 0.152 cu.m. per 100 sq.m.					10.080	Sqm	34.00	Rs.	342.72
12	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour. (ii)20 mm thick					19.080	Sqm	219.00	Rs.	4,178.52
13	Applying decorative cement based paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or concrete surface) as per manufacturer's specification. TWO COAT					165.685	Sqm	49.00	Rs.	8,118.57
									Rs.	1,87,907.37
									ADD GST =12%	Rs. 22,548.88
									TOTAL AMOUNT WITH GST	Rs. 2,10,456.25
									ADD CESS =1%	Rs. 2,104.56
									TOTAL AMOUNT WITH GST +CESS	Rs. 2,12,560.81
									Grand Total=	Rs. 2,12,560.81

Say Rs.212560

